

5-16-10W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY MAGNOLIA PETROLEUM CO.

SEC. 5 T. 16 R. 10W

FARM J. Haska

NO. 6

LOC. NW SE SW

TOTAL DEPTH 3280 K.B.

COMM. 1-24-51

COMP. 2-13-51


SHOT OR TREATED

CONTRACTOR Barnett Drilling Co., Inc.

ISSUED 3-24-51

COUNTY Ellsworth

KANSAS



CASING

8 5/8" 408' cem. w/225 sx
 5 1/2" 3259' cem. w/150 sx

ELEVATION 1790 DF

PRODUCTION 24 BO & 192 BWPD

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil	40
clay & shale	110
sand	205
shale & shells	300
blue shale & shells	408
shale, shells & redbed	585
anhydrite	613
shale & shells	1120
salt	1300
shale & shells	1325
shale & lime	1745
lime	1810
lime & shale	2680
lime	2745
lime & shale	2925
lime	3280 K.B.
Total Depth	

Tops: K.B.

Lansing 2934

Arbuckle 3258

Acidized w/1250 gals. acid.