

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Mardock,

Wichita, Kansas


6-16-10W

Company - SHIELDS & ANSCHUTZ  
 Farm - Adeline Barclay No. 1

SEC. 6 T. 16 R. 10W  
 NE SW SW

Total Depth. 3352 R.B.  
 Comm. 3-10-50 Comp. 3-25-50  
 Shot or Treated.  
 Contractor. Honaker Drlg Co.  
 Issued. 5-13-50

County. Ellsworth  
 KANSAS



CASING:

8 5/8" 208 cem. w/110 sx.  
 5 1/2" 3343 cem. w/50 sx.

Elevation. 1873

Production. Swabbed 100 bbls in  
 7 hrs.

Figures Indicate Bottom of Formations.

port rock & sand	40
shale blue	209
shale & lime	585
red bed	676
anhyd.	705
lime & shale	1371
lime	1595
lime & shale	1800
lime	1915
lime sdy	1960
lime	2076
lime & shale	2720
lime	2880
lime & shale	2972
shale	3020
lime & shale	3042
lime	3340
chert	3342
dolo.	3352
Total Depth	

Tops:	
Anhyd.	676
Topoka	2665
Hobner	2915
Toronto	2933
Douglas	2949
Lansing K.C.	3027
Arbuckle	3342

Notes:

The following porous zones were noted:  
 Topoka 2739-45 No show  
 2859-62 " "  
 Lansing K.C. 3030-33 " "  
 3060-73 " "  
 3136-49 " "  
 3215-21 " "  
 Arbuckle 3342-52 show of oil

D.S.T. tested 3342-3352. Tool open 20 mins.  
 Rec. lgt blow for 3 mins. Recovered 10' slightly  
 oil cut mud with good odor.