


KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 053 — 20,590
County NumberState Geological Survey
WICHITA, BRANCH

S. 7 T. 16 R. 10 E W

Loc. C S2 NW NW

County Ellsworth

640 Acres
N

Elev.: Gr. 1884

DF 1287 KB 1889

Operator

Cloud Exploration, Inc.

Address

231 West 20th St. Concordia, Ks. 66901

Well No.

#7

Lease Name

Anna Harbacek

Footage Location

900

feet from (N) line

650

feet from (W) line

Principal Contractor

Wilson Exploration & Drilling Inc.

Geologist

Toby Elster

Spud Date

APR. 24, 1980

Date Completed

APR. 30, 1980

Total Depth

3371

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

None

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Geologist Recd. to test	10"	8 5/8	28	350	Portland CIA	120	2% G-2 3% C-2
	7 7/8	4 1/2	9.5	3370	A Portland	75	none

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			6-4-80 5	Large	3368 1/2 to 3370 1/2
			6-24-80 4	Large	3367 to 3371

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8 O.D.	3360	7

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 G + 16 INHIB. 6-3-80 Went into Comp. instead of ARKALIE	3370
150 G + 1 INHIB 6-7-80	3370
6-16-80 Squeeze Job Comp. 100 SK Portland 4316. H-16-9	3370 to 3371
6-18-80 350 G Acid 16 INHIB 2368 G water	3367 - 3371

INITIAL PRODUCTION

Date of first production 7-23-80		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 3 bbls.	Gas MCF	Water 125 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s) Aband. 8-4-80		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator <i>Cloud Exploration INC.</i>		DESIGNATE TYPE OF COMP.: <u>(OIL)</u> GAS, DRY HOLE, SWDW, ETC.:
Well No. <i>7</i>	Lease Name <i>ANNA HARBACH</i>	<i>OIL - Aband.</i>
<i>S 7 T 16 R 10 W</i>		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<i>Heebner</i>	<i>2930</i>			
<i>Toronto</i>	<i>2949</i>			
<i>Douglas Shale</i>	<i>2967</i>			
<i>Brown Lime</i>	<i>3031</i>			
<i>Lansing</i>	<i>3051</i>			
<i>Base/Kansas City</i>	<i>3309</i>			
<i>Basal Penn. Cong.</i>	<i>3340</i>			
<i>Arbuckle</i>	<i>3368</i>			
<i>R.T.D.</i>	<i>3371</i>			
<i>Cable Tools T.D.</i>	<i>3381</i>			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	<i>Arnold A. Schen</i> Signature <i>Secy - Trust</i> Title <i>Oct. 6. 1980</i> Date
---------------	--

H20262K NO 7
W₃¹ - NW₄¹ - Sec 7 - T16 - R10W.

12

We spent a lot of money & time on this well, hoping we might make a producer, but to no avail.

So we abandoned all operations Aug 4, 80. And finally decided to sell all equipment. On Sept 11, 80 we had the tubing & rods pulled.

on Sept 30th 1980 we entered into agreement with

- Texas Tea oil & gas services for all interest in the lease of mineral interest And all production equipment.

- Texas Tea, oil & gas services purchased from Clont Explorations Inc. the above lease and all equipment.

Clont Explorations Inc.

By (Printed A. Schaefer) Secy-Treas.