

7-16-10W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BLACK-MARSHALL OIL CO.
Farm - A.Harbacek No. 1.

SEC. 7 T. 16 E10 W
NEc NW

Total Depth. 3315
Comm. 4-14-46 Comp. 4-26-46
Shot or Treated.
Contractor. Ferrell-Young Drig. Co.
Issued. 6-15-46

County. Ellsworth
KANSAS



Elevation. 1830

CASING:

8 5/8" 356' Cem.
5 1/2" 3298' Cem.

Production. Pot. 962 B

Figures Indicate Bottom of Formations.

shale & rock	200
sand	210
shale rock	285
shale & shells	325
pyrite & shale	350
lime & shale	356
shale, shells & red	
bed	560
shale & red rock	635
anhydrite	665
shale & shells	1380
lime	1440
shale & lime St.	1565
shale & lime	1650
sand	1670
shale & lime	1935
lime bro.	2140
shale & lime	2220
shale	2320
shale & shells	2480
shale & lime	2590
lime bro.	2755
shale & lime	2835
lime	2905
shale	2925
shale & shells	2970
lime	3185
shale & lime	3245
lime	3298
Arbuckle	3301
Rotary T.D.	
lime	3315
Total Depth (Cable)	

Tops:

Anhydrite	635
Lansing	2988
Base Kans. City	3297
Arbuckle	3297