

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


8-16-10W

CITIES SERVICE OIL CO.
Kralik "A" No. 5.

SEC. 8 T. 16 R. 10 W
CSW NW
660' N 660' E W $\frac{1}{4}$ Cor.

County. Ellsworth

Total Depth. 3335'
Comm. 7-10-43 Comp. 8-12-43
Shot or Treated.
Contractor. Corbett-Barbour Drlg.Co.
Issued. 10-30-43



CASING:
8 5/8" 330' Cem.
5 1/2" 3321' Cem.

Elevation.

Production. Phy.Pot.312 B.
No wtr

Figures Indicate Bottom of Formations.

lime	0-50
shale	80
shale & strk lime	330
red bed, shale, shells	665
anhydrite	700
shale & shells	1185
shale & salt	1275
lime & shale	1585
lime	1945
lime & shale	2060
lime brkn	2205
lime brkn & shale	2320
shale & lime	2665
lime	3318
cored dolomite(rec.4 $\frac{1}{2}$ ')	3323
cored dolomite(rec.1 $\frac{1}{2}$ ')	3329
3329 Rot.TD = 3327 SIM	
dolomite	3335
Total Depth.	

Corr. Top Arbuckle 3306
Penetration 29

Fillup:

1 bbl fluid per hr at 3325
At 3329 hole filled 390' to
520' in 4 hrs

500 Gals. Acid 8-5-43
1100 Gals. Acid 8-10-43
600 Gals. Acid 8-14-43
900 Gals. Acid 8-15-43