


CITIES SERVICE OIL CO.  
Kralik "B" No. 2.

8-16-10W  
SEC.8 T.16 R.10 W  
CNW SW  
660'S 660'E W $\frac{1}{4}$  Cor.

Total Depth. 3366'  
Comm. 3-27-43 Comp. 4-15-43  
Shot or Treated. 4-18-43 500 Gals.  
Contractor. Corbett-Barbour Drlg.Co.  
Issued. 6-12-43

County. Ellsworth



CASING:  
8 5/8" 325' Cem.  
5 1/2" 3358' Cem.

Elevation.

Production. Phy.Pot.169 B.  
No wtr

Figures Indicate Bottom of Formations.

shale & shells	0-325
shale	480
shale, red bed, shells	615
anhydrite	655
shale & shells	865
shale	1000
shale & shells	1150
salt	1280
salt & shale	1300
shale & shells	1370
lime & shale	1436
anhydrite	1515
shale & lime	1575
lime	1676
lime & shale	1770
lime	1883
lime & shale	2080
lime brkn	2195
lime & shale	2375
lime brkn	2467
shale & lime	2640
lime	2950
shale & lime	2990
shale	3070
lime	3317
lime & shale	3342
lime	3348
lime & shale cored (rec. 3')	3352
lime & shale	3356
lime	3358
3358 Rot. TD = 3358 SIM	
lime	3366
Total Depth.	

Top Arbuckle 3344  
Penetration 22

Fillup: 60' oil in 45 min.  
80' oil in  $1\frac{1}{4}$  hrs.  
450' oil in 7 hrs