

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

7-16-10W

Company - ALPINE OIL & ROYALTY CO., INC.

Farm - Jezek

No. 2.

SEC. 7

T. 16

R. 10 W

NE NW SE

150' N of CE $\frac{1}{2}$ NW SE

Total Depth. 3346'

Comm. 8-31-44

Comp. 10-7-44


Shot or Treated.

Contractor.

Issued. 1-6-45

County. Ellsworth

KANSAS



Elevation. _____

Production. Pmp 89 BO, NoWtr

CASING:

5 $\frac{1}{2}$ " 3341' Cem.

Figures Indicate Bottom of Formations.

post rock	40
shale & shells	130
shale & shells	270
sand	300
shale & shells	358
reamed	358
shale & shells	475
red beds	600
shale & shells	665
anhydrite	685
shale & shells	1410
lime	1550
lime hrd	1630
shale & shells	1850
lime	1920
shale & lime	2000
shale & shells	2255
shale	2330
lime	2370
shale & lime	
brkn	2435
shale & shells	2625
lime	2985
shale	3025
lime	3285
shale & cong.	3330
dolomite	3332
Rotary total depth	
corrected drill	
pipe measure-	
ment	3332 = 3342
cable tools	
dolomite	3346
Total Depth	

Tops:

Lansing-Kans City 3022

"Sooy" Congl 3317 Corr.

Arbuckle 3340

Pay 3340-3346

500 Gals. Acid