

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas


7-16-10W

Company - HERNDON DRLG. CO.
 Farm - Jezek No. 2.

SEC. 7 T. 16 R 10 W
 SW SE SE

Total Depth. 3400
 Comm. 10-10-45 Comp. 10-25-45
 Shot or Treated.
 Contractor.
 Issued. 12-15-45 Rotary O-3393

County. Ellsworth
 KANSAS



CASING:
 8 5/8"
 5 1/2"

372' Cem.
 3390' Cem.

Elevation. 1907 ft

Production. Pot. 5 B plus
 40% Wtr.

Figures Indicate Bottom of Formations.

shale & shells	0-280
sand	335
shale & shells	1430
lime & shale	1995
shale & shells	2085
lime	2185
shale & lime	2375
lime	2435
lime & shale	2765
lime	2835
lime brkn	2895
lime	3246
lime & shale	3395
lime	3400
Total Depth	

Tops:

Lansing-K.C. Limestone	3055
Oolitic & slightly oolitic, slightly porous limestone. No oil stain 3073-76	
Oolitic limestone with poor to fair porosity and no oil stain 3166-82	
Slightly oolitic, slightly porous limestone. No oil stain 3246-52.	
Weathered Simpson	3384
Arbuckle Dolomite	3389
light brown, medium finely crystalline dolomite w/sli por. & oil stain & a faint oil odor, 3389-93	