

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Plotted J.S.

8-16-10W

CITIES SERVICE OIL CO.
Kralik No. 2.

SEC. 8 T. 16 R. 10W
CWL NE NW
660'S 991'W of N $\frac{1}{2}$ Cor.

Total Depth. 3339'
Comm. 5-29-41 Comp. 6-18-41
Shot or Treated.
Contractor. Corbett-Barbour Drlg. Co.
Issued. 7-19-41

County. Ellsworth



CASING:

8 5/8" 380' Cem.
5 1/2" 3330' Cem.

Elevation.

Production. Echo. Pot. 1886 B.
No wtr

Figures Indicate Bottom of Formations.

surface lime & clay	0-45
shells & lime	90
sand & clay	302
iron pyrite	306
lime	380
shale & shells	588
red bed	672
iron pyrite	680
shells & shale	1125
salt & shells	1159
salt	1175
shale	1455
shale & shells	1485
lime	1525
lime w/strks shale	1548
shells & shale	1618
lime brkn & shale	1630
lime	1651
lime brkn	1752
lime	1941
lime brkn	2098
shale & shells	2190
lime	2243
shale	2375
lime	2405
shale & shells	2422
shale	2566
lime brkn	2676
lime	2710
lime brkn	2721
shale	2740
lime	3316
dolomite cored	
(rec 2 $\frac{1}{2}$ ')	3322
dolomite cored	
(rec. 4')	3327
3327 Rot. TD=3331 SLM	
dolomite	3331 - 3339
Total Depth.	

Fillup: 600' oil in 1 hr
1800' oil in 2 $\frac{3}{4}$ hrs
2800' oil in 5 $\frac{1}{4}$ hrs
3100' oil in 8 $\frac{1}{4}$ hrs

800 Gals. 6-19-41
1200 Gals. 6-20-41