

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

J.W.


8-16-10W

GULF OIL CORP.
W.A.Svoboda No. 3.

SEC.8 T.16 R. 10W
CW $\frac{1}{2}$ NE SE

Total Depth. 3337'
Comm. 8-22-40 Comp. 9-10-40
Shot or Treated. 9-10-40 2000 Gals.
Contractor.
Issued. 12-7-40

County. Ellsworth



CASING:
8 5/8" 293'
5 1/2" 3317'

Elevation.

Production. Pot.143 B.
420 BW

Figures Indicate Bottom of Formations.

clay, shale, shells	215
shale & shells	295
shale & red bed	385
shale & red rock	395
wtr sand	455
shale & red rock	610
anhydrite	660
shale & red rock	805
shale & red bed	965
shale & shells	1095
salt & shells	1320
lime brkn	1755
lime	1860
shale & lime	1905
shale & shells	2575
lime	2650
shale & lime	2705
lime	2895
lime brkn	2990
shale & lime	3110
lime	3305
lime & shale green	3312
Arbuckle dolomite	3337
Total Depth.	

Arbuckle lime 3316-3337

Note: 8 5/8" 1st set at 298'
This casing used in first hole
which was lost at depth of 2150'
account crooked. Cemented with 75
sacks from bridge at 800' to
297' and tried to re-drill hole;
this attempt unsuccessful, plugged
hole. Skidded derrick 24' south
and drilled new hole from surface.
Drilling of first hole started
8-9-40, plugged 8-19-40