


GULF OIL CORP.
W.A. Svoboda No. 4.

SEC. 8 T. 16. R. 10 W.
CW $\frac{1}{2}$ SE SE

8-16-10W
Noted

Total Depth. 3376 $\frac{1}{2}$
Comm. 9-28-41 Comp. 10-25-41
Shot or Treated.
Contractor.
Issued 3-28-42

County Ellsworth.



CASING.

13" 305' cemented
85/8" 3365 $\frac{1}{2}$ ' cemented.

Elevation.

Production Pot. 295 B.
Drawdown

Figures Indicate Bottom of Formations.

cellar	8 $\frac{1}{2}$	shale and lime shells	2303
surface soil&sand rock	93	broken lime and shale	2347
surface rock	110	shale and lime shells	2371
clay and shells	210	lime	2376
shells	265	shale shells and lime	2380
water sand	280	lime	2400
shells	295	shale	2440
shale and shells	320	shale and limo shells	2450
shells	338	lime	2521
shale and lime shells	525	limo hard and shale	2533
red bed and shells	678	lime	2554
anhydrite	791	shale	2585
shale and shells	810	lime	2595
red bed and shells	827	broken lime and chert	2600
red bed	845	limo	2641
anhydrite	860	lime hard and shale	2703
shale and shells	931	lime hard and shells	2753
shale and lime shells	1024	lime	2865
salt	1341	lime and shells	2885
salt and shale	1352	lime	2951
shale, shells and lime	1372	shale red and lime	2962
shells and shale	1404	shale grey and lime	3005
anhydrite and lime	1420	lime hard	3012
shale and lime shells	1450	shale and lime	3054
anhydrite lime	1495	lime	3133
broken lime and shale	1558	mod soft lime	3150
lime	1569	lime hard	3181
broken sand and lime	1579	lime mod soft	3185
broken lime	1590	lime	3297
shale and lime shells,	1595	shale	3303
lime	1608	lime hard	3320
broken lime and shale	1623	limo	3357
sdv lime	1651	shale green	3365 $\frac{1}{2}$
broken lime and shale	1715	Arbuckle lime	3376 $\frac{1}{2}$
broken lime	1732	Total Depth.	
lime and shale	1747		
lime and sand	1762	Arbuckle lime	3364 $\frac{1}{2}$ -3376 $\frac{1}{2}$
shale and lime	1782		
lime	1800		
shale and lime shells	1828	Acidized 10-24-41 with 2000 gal.	
broken lime and shale	1929		
lime and shale strks	1937		
lime	1980		
lime and shale	2000		
lime	2024		
shale and lime shells	2136		
broken lime and shells	2163		
broken lime	2180		
lime	2202		
shale and lime shells	2210		
shale	2237		