

9-16-10W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company H.E. ALEXANDER
Farm Minnie Boye No. 1

SEC. 9 T. 16 R. 10W
NW SW SW
Approx. 150' fr NL 500' fr
WL SW
County Ellsworth
KANSAS

Total Depth 3388'
Comm. 1-15-53 Comp. 2-2-53
Shot or Treated.
Contractor Salina Drlg. Corp., Inc.
Issued 3-30-57


Casing:

8 5/8" 260' w/125 sx cem.
4 1/2" 3387.84' w/100 sx cem.

Elevation. 1892' DF

Production. 10 BO/NW

Figures indicate Bottom of Formations.



cellar-base-rotary

Table	8
sand	46
sand-shale	460
red beds	670
Anhydrite	695
shale-shells	1330
salt-shale-lime	1545
sand	1585
shale-lime	1675
lime-shale	2645
lime	2650
lime-shale	2720
lime	2815
lime-shale	2880
lime	2920
shale-lime	3072
lime	3120
shale-lime	3177
lime	3230
shale-lime	3302
lime	3374
lime-shale	3388
Total Depth	

TOPS:

Huebner shale	2935
Toronto	2954
B/Oread	2963
Douglas sand(shaley)	2987
Brown Lansing	3035
Lansing-Kansas City	3053
B/Kansas City	3347
Simpson shale	3363
Simpson sand	3365
Arbuckle	3386