


9-16-10W

THE AYLWARD PROD. CO.-DUWE & FARRIS.
 Boye No. 2

SEC. 9 T. 16 R. 10W.
 CEL NW SW

Total Depth. 3346
 Comm. 10-19-40 Comp. 11-3-40
 Shot or Treated.
 Contractor. The Aylward Prod. Co.
 Issued. 12-21-40

County Ellsworth.



CASING.

10" 280' cemented
 5 1/2" 3338' cemented.

Elevation. 1849

Production. Pot. 141 B.
 Temporary.

Figures Indicate Bottom of Formations.

surface clay	20		
shale	230		
sand	310		
red rock	425	lime	3327
shells and shale	492	shale	3337
iron	500	lime	3338
red rock iron folding in	515	Arbuckle lime	3346
shells and shale	620	Total Depth.	
lime shells	640		
anhydrite	675	Oil from 3340 to 3346	
shale and red rock	940	Filled up 2800' in 10 hours.	
shells and shale	1102		
salt	1235		
shale and shells	1435	Top Kansas City lime	3022
lime	1450		
lime and shale breaks	1570		
lime	1605		
broken lime	1765		
lime	1902		
broken lime	1950		
shale and lime	2050		
lime	2095		
shale and shells	2145		
broken lime	2255		
shale and lime	2340		
lime	2360		
broken lime	2390		
shale	2410		
lime	2465		
broken lime	2550		
lime	2615		
lime	2625		
shale	2640		
lime	2960		
lime and shale	3010		
shale brown	3022		
lime	3105		
lime broken	3130		
lime hard	3160		
lime	3215		
lime broken	3270		
lime and shale	3305		