

Plotted


9-16-10W^{I.P.}

DUWE & FARRIS
Boye No. 1.

SEC. 9 T. 16 R. 10W
CWL SW SW

Total Depth, 3371'
Comm. 11-1-39 Comp. 12-24-39
Shot or Treated.
Contractor.
Issued. 1-6-40

County. Ellsworth



CASING:
10" 360'
5 9/16" 3365'

Elevation.

Production. Pot. 6188 B.
Echometer

Figures Indicate Bottom of Formations.

shale & lime 365
iron, sand, shale 520
shale red 670
anhydrite 702
shale 810
shale & lime 912
shale blue, lime shells 1080
shale & shells 1110
salt 1295
shale & shells 1370
lime & chert 1402
lime 1479
shale & lime 1545
lime 1663
shale & lime 1695
sdy lime 1715
lime 1738
shale sticky 1785
lime brkn 1805
lime 1830
shale & shells 1897
lime 2065
lime brkn 2106
sdy lime 2115
shale 2140
shale & shells 2175
shale 2282
lime 2300
shale & lime 2320
shale & shells 2390
shale & lime 2457
lime 2467
shale & lime 2490
shale & shells 2591
lime 2610
shale & lime 2638
lime 2665
shale 2680
lime 2958
red rock & shale 2985
shale blk 3024
lime brkn 3029
lime Top K.C. 3029-3048
lime 3351

Simpson shale 3365
Arbuckle lime 3369
oring lime 3371
recovered saturated core
Total Depth.

Top Arbuckle 3364