


9-16-10W

DUWE & FARRIS
 Minnie Boye No. 2

SEC. 9 T. 16 R. 10W.
 CEL SW SW

Total Depth. 3362
 Comm. 1-2-41 Comp. 2-7-41
 Shot or Treated.
 Contractor.
 Issued 3-8-41

County Ellsworth.



CASING.

85/8" 361'8" surface
 5 1/2" 3359'

Elevation.

Production. Pot. 2712 B.

Figures Indicate Bottom of Formations.

cellar	55
shale and shells	225
sand shells	355
shale and shells	406
shale	470
iron	478
shale red and blue	653
anhydrite	680
shale	685
shale and shells	1095
salt	1350
shale and shells	1368
lime and shale	1520
lime	1550
broken lime	1630
lime and shale	1680
shale and shells	1790
lime and shale	1824
lime	1930
lime and shale	2038
shale and shells	2094
lime	2128
shale	2145
shale and shells	2315
shale	2360
lime	2385
shale	2410
lime and shale	2518
shale and shells	2595
lime and shale	2690
shale	2700
lime	2992
shale	3012
lime	3343
cherty conglomerate	3345
Simpson shale	3356
lime	3361
cored lime	3362

Recovered saturated core.

Drilled plug. Oil filled
 1900' in 30 minutes.
 2500' in 1 hour
 2900' in 3 hours.

Top Arbuckle 3356

Total Depth.