

P/

9-16-10W

DRILLER'S WELL LOG

ATE COMMENCED: 5-18-80
ATE COMPLETED: 5-23-80

R. R. Ayesh
Kozisek #1
C N/2 N/2 SE/4 Sec. 9-16-10
Ellsworth County, KS

ELEVATIONS 1800' K.B.
1795' G.L.

FORMATION DATA

Anhydrite 591 610

2942-2960' Lime & Shale
2960-3236' Lime
3236-3289' Lime & Shale
3289-3296' Shale
3296-3314' Sand
3314' RTD

Anhydrite 591

Brown Lime 2942'
Kansas City 2960'
Base Kansas City 3236'
Simpson Shale 3289'
Simpson Sand 3296'
RTD 3314'

SURFACE PIPE:

Set @ 337' 8 5/8" 28#
used Casing w/175 sks
60/40 Pozmix 2% Gel 3% c.c

PLUGGING:

Hvy mud to 540' w/40 sks
50/50 Pozmix 2% Gel
Mud to 330' w/25 sks
Mud to 40' w/1/2 sks hulls &
10 sks. 5 sks in rathole
5-23-80

AFFIDAVIT

TATE OF KANSAS)
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his