

9-16-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GRANT OIL COMPANY
Farm- Lank No. 1

SEC. 9 T. 16 R. 10W
NW SW NE

Total Depth. 3254'
Comm. 6-22-57 Comp. 6-30-57
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg. Co.
Issued. 5-23-59

County Ellsworth
KANSAS



CASING:

3 5/8" @ 280' cem. w/175 sx.
5 1/2" @ 3250' cem. w/100 sx.

Elevation. 1773' RB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

shale & shells	150	
sand & shale	235	
shale	280	
shale & shells	420	
red bed	550	
anhydrite	575	
shale & shells	950	
shale & salt	1130	
shale & shells	1250	
broken lime	1365	
lime & shale	1765	
shale & lime shells	1880	
shale & shells	2460	
shale & lime shells	2535	
lime & shale	2695	
brown lime	2915	
lime	3229	
Core	3242	
Simpson shale & Arbuckle	3251	RTD
Simpson shale & Arbuckle	3254	
Total Depth		

TOPS: SCOUT

Topeka	2494
Heebner	2792
Toronto	2813
Brown Line	2895
Kansas City	2910
Arbuckle	3249