

9-16-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- BENNETT & ROBERTS DRILLING CO.
Farm- Skalicky No. 1

SEC. 9 T. 16 R. 10W
Approx. SW NW NW

Total Depth. 3258
Comm. 8-26-56 Comp. 9-5-56
Shot or Treated.
Contractor.
Issued. 12-29-56

County Ellsworth
KANSAS



CASING:
8 5/8" 310' cem w/185 sx.
5 1/2" 3255' cem w/ 75 sx.

Elevation. 1795 D.F.

Production. 25 BOPD

Figures indicate Bottom of Formations.

subsoil, clay	70
red bed	180
sand	220
shale gry	290
shale blue, shells	310
shale blue	395
sand, hrd strks	435
shale, shells	520
red bed	600
anhydrite	620
red bed, shale, shells	780
shale, shells	1100
shale, shells, lime strks	1395
lime	1585
lime, shale strks	1730
lime	1850
shale, lime shells	2030
lime, shale	2450
shale, lime strks	2585
shale, lime	2789
lime	2855
shale, lime	2973
lime	3244
shale, lime RTD	3256
lime	3258
Total Depth	

Tops: R.B. Meas.		
Cimarron Anhydrite	600	(Drillers)
Heebner shale	2819'	
Toronto lime	2840	
Douglas shale	2848	
Brown Lime	2926	
Lansing K. C.	2941	
Simpson shale	3247	
Arbuckle	3254	

No electric logs run.

No cores taken.

No Drill stem tests.