

DESCRIPTION OF WELL AND LEASE

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct.

Richard Brown 102 Myers St
☒ Other (explain). Holywood, Ks.
 (purchased from city, R.W.D. #)

514927

Operator Name ...Gable Oil Company... Lease Name...Skalicky... Well #...5....

Sec. 9..... Twp. 16..S.... Rge. 10..... ☐ East ☒ West County.....Ellsworth.....

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☒ Yes ☐ No
Samples Sent to Geological Survey ☐ Yes ☐ No
Cores Taken ☐ Yes ☐ No

Formation Description
☒ Log ☒ Sample

Drillstem test # 1, 13257 - 3309
Test tool open 30 min., closed 30 min.,
open 30 min, closed 30 min. Blow off
bottom bucket in 3 minutes. No gas to
surface. Recovery was 5 foot of oil cut
mud and 775 feet of salt water.
Pressures:
I HP 1652, I FP 37, IFFP 1072, FIFP 274,
FFP 384, FCIPI 072, FHP 1561

Name	Top	Bottom
Heebner	2851	-1018
Brown	2951	-1118
Lansing	2974	-1141
Arbuckle	3301	-1468
TD	3739	

METHOD OF COMPLETION

☒ Open Hole ☐ Perforation
☐ Other (Specify)

Intervals of interest. Arbuckle
Off white to tan sacrosic dolomit
that contained traces of light
brown free oil, var. colored
shale & opaque chert, some
ollicastic.

CASING RECORD ☒ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	10 3/4"	8 5/8"	20	3331	Common	200	2% sal. 2% cc
Production	7 7/8"	5 1/2"	14.5	3367.63	Reg Poz	250	more

PERFORATION RECORD

Shots Per Foot	Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
		Acid HOWCO 1500 gal 15%	3364 to
		Open Hole	3739

TUBING RECORD	Size	Set At	Packer at	Liner Run	☐ Yes ☒ No
3 1/2" Eue Daolined		3331	3334		
Date of First Production	Producing Method				
	☐ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (explain)...SWD....				