

9-16-10w E.M.


PRUNTY PRODUCTION CO.
Henry Skalicky No. 1.

SEC. 9 T.16 R.10W
CW $\frac{1}{2}$ NW NW

Total Depth. 3272'
Comm. 4-28-40 Comp. 5-26-40
Shot or Treated. 7000 Gals. Acid
Contractor.
Issued. 8-10-40

Rotary O-3260
Cable 3260-72

County. Ellsworth



CASING:
10 $\frac{3}{4}$ " 343'8"
5 $\frac{1}{2}$ " 3257'7"

Elevation.

Production. Pot. 3000 B.
no wtr

Figures Indicate Bottom of Formations.

surface clay	30
shale & shells	337
pyrite of iron	343
shale & iron	386
shale & shells	557
red rock	576
lime	605
red bed	625
shale & shells	1370
lime	1390
shale & shells	1410
lime	1739
lime sdy	1825
lime	1907
lime sft	1992
shale & shells	2412
shale	2435
lime sdy	2485
lime	2726
lime brkn	2800
lime hrd	2830
lime brkn	2855
lime	2938
lime hrd	2956
lime	3073
lime hrd	3107
lime	3250
lime Arbuckle	3263
lime brown & sft	3269
dolomite Arbuckle	3272
Total Depth.	

Acidized w/7000 Gallons

Arbuckle dolomite 3269-72

Pot. 3000 B., gravity 45
no wtr