

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


10-16-10W

K & E DRILLING, INC. &
Company- CENTURY PRODUCTION CO.
Farm- Funk No. 6

SEC. 10 T. 16 R. 10W
SW NE NW

Total Depth. 3800
Comm. 11-9-55 Comp. 11-19-55
Shot or Treated.
Contractor. K & E Drilling, Inc.
Issued. 1-7-56

County Ellsworth
KANSAS



Elevation. 1859 RB

Production. S. W. D. W.

CASING:
8 5/8 @ 354' w/ 175 sx cmt.
5 1/2 @ 3503' w/ 100 sx cmt.

Figures indicate Bottom of Formations

surface clay	35
lime & shale	200
hard sand & shale	354
shale	415
sand & shale	550
red bed & shale	653
anhydrite	695
shale & shells	1400
lime	1515
lime & shale	2620
lime	2895
Heebner & Toronto	2938
Douglas	2945
sand & shale	3000
lime	3515
lime & chert	3759
lime	3800
Total Depth	

SCOUT TOPS:	
Anhydrite	653
Heebner	2892
Toronto	2911
Douglas	2922
Brown lime	2997
Lansing	3016
Base K. C.	3293
Shaley conglomerate	3329
Viola	3353
Simpson	3383
Arbuckle	3407