

IND. TERR. ILL. OIL CO.
M.Boyc No. 3

SEC. 16 T. 16 R. 10W.
CE $\frac{1}{2}$ SW NW

Total Depth. 3340.
Comm. 8-25-40 Comp. 9-24-40
Shot or Treated. 1000 gal 9-25-40 3340
Contractor. Glenn Drilling Co.
Issued. 11-2-40

County Ellsworth.

CASING.


Rotary and Cable.

103/4" 499'
7" 3327'

Elevation.

Production. Pot. 58,467 B.
Deptho.

Figures Indicate Bottom of Formations.



cellar	10	lime and shale broken grey white	
surface boulders and clay white		mod	2505
yellow and med	25	lime white hard	2525
shale and sand shells	235	shale lime grey mod	2580
sand white soft	285	shale and shells grey mod	2595
sand white hard	380	lime white hard	2621
sand white med	485	lime white hard	2630
shale blue hard	506	sdv shale grey mod	2642
red bed red	615	lime white hard	2675
red bed red soft	645	shale grey mod	2695
anhydrite and shale streaks white		lime white hard	2767
blue hard	675	lime white hard	2778
red bed and shale & shells red grey		cherty strks and lime rough wh	
soft	845	hard	2784
red bed shells red med	1062	broken lime	2800
shale and shells blue med	1135	lime white hard	2826
salt & shale strks wh and blue		shale lime shells grey wh mod	2886
soft	1285	lime white hard	2910
shale and shells blue mod	1330	broken lime shale grey mod	2923
shale and shells blue med	1365	shale lime shells wh grey and	
anhydrite and shale streaks white		mod	2945
hard	1454	lime white hard	3030
shale and shells blue mod	1485	shale and lime broken grey wh	
lime white hard	1510	mod	3053
shale blue mod	1530	lime white hard	3103
shale and anhydrite grey mod	1600	lime white soft	3136
shale red soft	1625	lime white hard	3157
lime brown med	1640	lime and shale strks wh grey	
lime brown mod	1695	mod	3179
shale and shells grey mod	1747	lime grey hard	3191
shale and shells grey mod	1837	lime white mod	3199
lime and shale strks white		lime white hard	3242
blue mod	1915	lime and shale strks white grey	
lime and shale streaks white blue		mod	3262
mod and hard	1990	lime and shale strks white	
shale and lime shells grey mod	2028	grey mod	3272
shale blk mod	2036	lime wh and grey mod	3296
lime grey hard	2060	lime white hard	3307
shale and lime shells grey blk		lime mod	3331
soft	2072	3331 equals 3330	
shale and lime shells blue wh		lime hard	3334
mod and soft	2155	shale green	3336
lime grey mod	2168	lime soft	3338
shale sticky blue soft	2201	lime grey hard	3340
lime grey white hard	2228	Total Depth.	
shale and lime strks grey white			
mod	2265		
shale and lime grey mod	2290		
lime white hard	2330		
shale grey mod	2350		
shale and lime shells grey			
white mod	2423		
shale and shells grey soft	2435		
lime brown white hard	2456		