


IND. TERR. ILL. OIL CO.
John Boye No. 1.

16-16-1000
SEC. 16 T.16 R.10W
CEL NE NW

Total Depth. 3344'
Comm. 5-27-40 Comp. 6-14-40
Shot or Treated.
Contractor. Glenn Drlg.Co.
Issued. 7-20-40 Rotary & Cable

County. Ellsworth



CASING:
10 3/4" 543'7"
7" 3338'

Elevation.

Figures Indicate Bottom of Formations. Production. Pot.15 B.
(Minimum well)

cellar	10	lime gy hrd	3064
shale blue & clay yellow	180	lime wh hrd	3078
shale&sand strks gy med	520	sdv shale & lime shells	
shale&sand shells gy med	530	gy wh med	3086
red bed & shells red med	548	lime wh hrd	3094
red bed red sft	660	sdv lime wh sft	3120
shale & red bed green & red med	810	lime wh hrd	3182
shale & red bed strks gy sft	1105	lime & shale strks wh med	3198
salt & shale wh & gy med	1275	lime & shale strks wh & gy hrd	3258
shale gy med	1830	lime wh hrd	3277
anhydrite & lime wh med	1420	shale & lime gy & wh med	3279
anhydrite&sdv lime wh med	1445	shale & lime gy med	3309
lime & brkn shale wh,gy med	1552	shale green hrd	3331
lime gy med hrd	1568	shale & shells green & wh hrd to sft	3341
shale gy med	1598	sand gy sft	3342
lime & shale gy med	1623	Arbuckle lime gy sft	3343
sdv lime & shale gy hd	1672	Corrected 3343 equals	3339
brkn lime & shale gy med & sft	1720	lime sft gy	3339- 3342
lime wh hrd	1765	lime gy hrd	3344
shale & lime shells gy, wh med	1800	Total Depth.	

1st 4-hr production 20 B0,
19 Bbls. wtr

brkn sdv lime & shale gy med to hrd	1857	gy,wh,med & hrd	2746
lime & shale wh & gy med	1878	lime & shale strks wh, gy hrd	2806
lime sdv & shells wh & gy med	1895	lime & shale wh & gy hd	2825
lime & brkn shale gy med	1922	lime wh med hrd	2860
lime brkn & shale wh & gy med	2040	lime wh med	2872
lime brkn & shale gy med	2120	lime sdv wh hrd	2891
shale & shells gy med	2395	lime & shale wh,gy med	2903
lime wh med	2405	shale & lime shells gy wh sft	2957
shale sticky & lime shells gy & wh hrd	2453	shale & lime shells dk gy & wh sft	2984
shale & shells gy med	2535	lime brkn & shale wh & gy med	3010
shale & lime strks gy, wh med	2573	lime wh med	3028
shale & shells gy,wh sft	2647	shale & lime brkn gy & wh sft	3042
shale & brkn lime shells gy & wh med	2698		
shale & sdv lime strk			