

16-16-10W

IND. TERR. ILL. OIL CO.

John Boye No. 2.

SEC. 16
CWL NE NW

T. 16

R. 10W

Total Depth. 3343'

Comm. 9-26-40

Comp. 10-16-40


Shot or Treated.

Contractor. Glenn Drilg. Co.

Issued. 11-30-40

Rotary 3343

County. Ellsworth



CASING:

10³/₄" 445'
7" 3303'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	10	lime	3338
surface boulders & clay	32	lime gy hd	3341
shale & sand shells blue	85	lime, water	3343
sand & shale	420	Total Depth.	
shale blue med	446		
red bed red med	456		
red bed	590		
red bed, shale red sft	840		
red bed & shells red sft	920		
shale gy med	970		
shale & shells blue med	1075		
shale & salt	1228		
salt, shells wh sft	1310		
shale & shells blue med	1387		
shale & shells gy med	1488		
sand & shale strks gy med	1516		
shale & anhydrite wh, gy hd med	1560		
shale	1638		
shale & sdy shells gy med	1685		
sand wh sft	1705		
lime & shale strks wh hd	1715		
shale blue med	1760		
lime brown hd	1778		
shale & lime strks gy, wh med	1828		
shale, lime strks wh, gy med	1908		
shale & shells gy med	1913		
lime wh med	1930		
shale sft	1962		
shale & shells gy med	2050		
shale gy sft	2080		
lime wh med	2092		
shale gy med	2182		
shale sdy gy sft	2302		
shale gy sft	2309		
lime wh hrd	2328		
shale & lime strks gy, wh med	2397		
shale gy med	2439		
lime brown hrd	2458		
shale & lime shells, blue, gy, med & sft	2520		
shale, lime wh, gy med	2600		
lime & shale strks, wh, gy, hd to med	2655		
lime & shale strks gy hd	2685		
lime, shale wh, gy hrd	2747		
lime	2806		
lime wh hrd	2931		
		lime wh hrd	3012
		lime sdy wh sft	3020
		lime wh hrd	3057
		brkn lime & shale, wh, gy med sft	3075
		lime wh sft	3099
		lime wh med	3121
		lime wh hrd	3195
		lime wh med	3228
		lime, shale wh hrd	3285
		shale & lime strks, gy, wh, med hd	3305
		3305-3306 '10" corrected	
		dolomite sdy, gy hd	3310
		shale green	3325
		shale green sft	3329