

15-16-10W
Ind

BARNETT OIL COMPANY X
WELL LOG - ALDEN NO. 2
A/O NE/4 NW/4 NW/4 SECTION 15-16S-10W
ELLISWORTH COUNTY, KANSAS

Date Started: 11- 8-57
Date Rotary Completed: 11-17-57

<u>From</u>	<u>To</u>	<u>Formation</u>
0	80	Post Rock
80	260	Shale
260	295	Sand
295	366	Shale
366	900	Shale and shells
900	1375	Shale
1375	1413	Anhydrite
1413	1500	Shale and shells
1500	1750	Shale and lime
1750	1865	Lime and shale
1865	1965	Lime
1965	2215	Shale
2215	2605	Lime and shale
2605	2715	Shale and lime
2715	2820	Lime and shale
2820	2935	Lime
2935	3050	Lime and shale
3050	3405 1/2	Lime (Total Depth)

Set 8 5/8", 21 1/2# s.s. casing at 365 1/2'
with 200 sacks of Portland Cement.

Set 5 1/2", 15.50# s.s. casing at 3406'
with 125 sacks of cement

JUN 1 8 1958
KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF SEDGWICK) ss.

I, F. H. Rousey, Office Manager of Barnett Oil Company, being duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.