

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. THE TEXAS COMPANY
Farm. F. J. Urbanek

No. 1

SEC. 15 T. 16 R. 10W
NW NW SE

Total Depth. 3431; PB 3419

Comm. 11-20-54


Comp. 12-13-54

County Ellsworth
KANSAS

Shot or Treated.

Contractor. Stickle Drlg. Co.

Issued. 2-12-55



CASING:

10 3/4" 288' cem. w/275 sx & 5 sx CC, circ.

7" 3430' cem. w/100 sx

Elevation. 1890 DF

Production. Pmp. 77 BO & 14 BW/
8 hrs.

Figures indicate Bottom of Formations.

clay & shale	75
sand	90
shale & shells	657
Anhydrite	738
shale & shells	1400
lime	1425
lime & shale	1670
broken lime	1805
lime & shale	1880
shale & broken lime	2005
shale & lime	2405
shale & sand	2435
shale & lime	2670
lime	2720
lime & shale	2797
lime	2950
Douglas shale	3020
lime & shale	3042
lime	3336
Conglomerate	3413
lime Arbuckle	3431
Total depth; PB 3419	

Tops:

Cimaron Dolomite	654
Tarkio	2368
Willard	2387
Topeka	2576
Heebner	2913
Toronto	2934
Douglas	2944
Brown Lansing	3020
Lansing	3321
Simpson	3353
Simpson sand	3366
Arbuckle	3403