

16-16-100
Plotted Tex s CO.
Plotted
C.R. 3Location. SE corner. SE $\frac{1}{4}$

Sec. 16 T.16 R. 35W

Casing Record.

County. Ellsworth.

JUL 9 1932

10" Farm. Kozisek No. 1
 20" 265 8 $\frac{1}{4}$ " 3134 Company. Gypsy Oil Co.
 15 $\frac{1}{2}$ " 510 65/8" Contr.
 12 $\frac{1}{2}$ " 1035 53/16" Comm. 3-16-32 Comp. 6-21-32
 Total Depth. 3385 Shot 50 Quarts Between. 3358-84
 Correspondence Regarding This Well Should Be Referred To.

Elevation. 1840

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 7-9-32

after shot Swabb 276 bbls oil in
7 hours.

Formation	Depth	Formation	Depth	Formation	Depth.
sand	2	lime	2020	shale	3320
shale	130	red rock	2024	lime red & blue shale	3332
red rock	200	lime	2035	lime blue and green	
shale	225	shale	2045	shale & chert	3343
red rock	240	shale	2075	shale red and green	3354
shale	250	lime	2085	dolomite	3369
sand water	265	shale	2100	dolomite	3385
shale	280	lime	2105	TD.	
sand water	360	shale	2120		
HFW 350		lime	2135	Note-	
shale	400	shale	2145	Log below 3320 has been	
sand water	425	lime	2155	corrected for SLM of 3371	
sdv lime	480	shale	2200	equals 3354 feet.	
sand water	485	lime	2205	Top of Siliceous lime 3354	
sdv lime	510	shale	2240		
shale	545	red rock	2245	6/6 T.D. 3369 Swab 137 bbls	
red rock	600	shale	2275	5 hours.	
sdv lime	605	shale	2285	6/9 T.D. 3380 swab 182 bbls	
2 BW 600		lime	2290	7 hours.	
red rock	690	shale	2365	6/17 T.D. 3385 Swab 194 bbls	
lime	710	lime	2380	7 hours.	
red rock	900	shale	2390	6/18 T.D. 3385 shot 50 qts	
shale green	945	sand 5 BW	2410	3358-84.	
red rock	990	shale	2425	6/21 T.D. 3385 After shot	
shale	1125	lime	2430	swabbed 276 bbls oil 7 hrs.	
salt	1350	lime	2450		
shale	1365	shale	2475		
salt	1385	shale	2490		
lime	1405	lime	2495		
salt and shale	1415	shale	2575		
lime	1430	lime	2590		
shale	1440	shale	2600		
lime	1490	shale and lime	2620		
red rock	1495	shale	2660		
lime shells	1525	lime	2700		
lime	1540	sdv lime	2725		
shale	1570	3 BW 2700-05			
lime	1590	lime	2760		
red rock	1615	shale	2765		
lime	1710	lime	2850		
sdv lime	1725	light show oil & gas	2845-55		
sand 5BW 1725-40	1740	lime	2880		
lime	1775	lime	2905		
sdv lime	1790	shale	2915		
red rock	1795	lime	2925		
lime	1810	red rock	2955		
sdv lime	1820	lime	2965		
2 BW 1815-20		lime	2970		
shale	1830	shale	3000		
red rock	1875	lime gas 3030	3085		
shale	1890	broken lime	3130		
red rock	1900	1 BW 3075-3130			
shale	1925	lime	3195		
broken lime	1950	lime	3225		
red rock	1960	broken lime	3230		
lime	1970	lime	3290		
red rock	1990	2 BW 3260-70			
lime	1995	shale	3295		
red rock	2000	lime	3315		