


16-16-10W

GULF OIL CORP.  
Anna Malir No. 1.

SEC. 16 T. 16 R. 10W  
NW SW SW NE  
630' fr SL 300' fr WL NE  $\frac{1}{4}$

Total Depth. 3322'  
Comm. 4-11-40 Comp. 5-2-40  
Shot or Treated.  
Contractor.  
Issued. 5-25-40

County. Ellsworth



CASING:  
8 5/8" 344'  
5 1/2" 3318'

Elevation.

Production. Pot. 7256B.

Figures Indicate Bottom of Formations. Senie Motor. Maximum  
3000B. No wtr

surface clay	90
shale blue	115
red bed	178
sand & gravel	230
red bed	265
shale gy & shells	352
clay, shale, red bed & shells	555
red bed & shale	610
anhydrite	635
shale & shells	1085
salt, shale, & shells	1270
shale	1290
lime brkn	1335
anhydrite	1425
shale	1445
shale & lime	1535
lime	1555
shale	1585
lime	1650
shale & lime	1690
lime sdy	1715
shale & lime	1760
lime	1787
shale	1810
red bed	1825
lime brkn	1835
shale	1865
shale & lime	1900
lime	1915
shale & lime	1960
lime	2020
lime brkn	2050
shale & lime	2300
lime brkn	2322
lime	2342
lime brkn	2395
lime	2420
shale & lime	2460
shale & shells	2540
shale & lime	2575
lime brkn	2617
lime Topeka	2685
lime	2880
slate & lime	2905

slate	2930
lime	3294
shale & sand hrd	3301
lime	3306
slate & lime	3316 $\frac{1}{2}$
shale green	3318
lime	3322
Total Depth.	

Arbuckle lime 3317-22