

16-16-10W  
Plotted Texas CO.

SEC. 16 T. 16 R. 10W.

NEC SE SE

SEP 15 1934

GYPSY OIL COMPANY.


Kozisek No. 2.

Total Depth. 3393 $\frac{1}{2}$   
Comm. 6-1-34 Comp. 7-17-34  
Shot or Trea ted.  
Contractor.  
Issued. 9-15-34.

County. Ellsworth.

CASING.

20" 294' 10" 2015'  
15 $\frac{1}{2}$ " 518' 8 $\frac{1}{2}$ " 2975'  
12 $\frac{1}{2}$ " 1075' 65/8" 3358 UR 3377 UR 3389



Elevation. 440

Figures Indicate Bottom of Formations

Production. Pump 200 B.O.  
and 110 B.W. 24Hr.  
Potential test.

|                            |      |                  |      |
|----------------------------|------|------------------|------|
| soil                       | 10   | lime             | 1910 |
| lime                       | 20   | shale            | 1925 |
| shale                      | 130  | lime             | 1935 |
| sdv shale                  | 160  | red rock         | 1940 |
| red rock                   | 200  | lime             | 1950 |
| red rock                   | 240  | shale            | 1965 |
| shale                      | 265  | lime             | 1975 |
| sand                       | 290  | red rock         | 2015 |
| HFW 265-90                 |      | lime             | 2065 |
| shale                      | 295  | shale            | 2080 |
| sand                       | 305  | lime             | 2090 |
| red rock                   | 310  | shale            | 2210 |
| shale                      | 340  | lime             | 2220 |
| sand watr                  | 350  | red rock         | 2255 |
| shale                      | 400  | lime             | 2260 |
| sand                       | 490  | shale            | 2270 |
| iron                       | 495  | red rock         | 2285 |
| sand and iron              | 505  | shale            | 2315 |
| shale                      | 535  | lime             | 2320 |
| red rock                   | 600  | sdv shale        | 2350 |
| lime                       | 615  | shale            | 2370 |
| sdv lime 2 BW              | 625  | lime             | 2390 |
| red rock                   | 665  | shale            | 2405 |
| lime                       | 700  | lime             | 2430 |
| red rock                   | 905  | 3 BW 2410-20     |      |
| shale                      | 960  | shale            | 2445 |
| red rock                   | 1000 | lime             | 2465 |
| shale                      | 1120 | shale            | 2470 |
| salt                       | 1345 | lime             | 2475 |
| shale                      | 1350 | shale            | 2485 |
| salt                       | 1395 | lime             | 2510 |
| shale                      | 1405 | shale            | 2595 |
| shale and shells           | 1500 | lime             | 2615 |
| red rock                   | 1515 | shale            | 2625 |
| lime                       | 1550 | lime             | 2750 |
| shale                      | 1560 | lime             | 2755 |
| lime                       | 1610 | sdv lime         | 2765 |
| red rock                   | 1620 | lime             | 2775 |
| lime                       | 1650 | shale            | 2795 |
| shale                      | 1655 | lime             | 2835 |
| lime                       | 1730 | shale            | 2845 |
| sand                       | 1750 | lime             | 2900 |
| 2 $\frac{1}{2}$ BW 1720-30 |      | lime             | 2925 |
| shale                      | 1760 | show oil 2855-60 |      |
| red rock                   | 1770 | shale            | 2930 |
| lime                       | 1795 | lime             | 2950 |
| red rock                   | 1800 | red rock         | 2960 |
| lime                       | 1830 | lime             | 2980 |
| shale                      | 1845 | shale            | 3025 |
| red rock                   | 1850 | lime             | 3065 |
| lime                       | 1870 | shale            | 3080 |
| 2 BW 1850-60               |      | lime             | 3285 |
| shale                      | 1880 | shale            | 3302 |
| lime                       | 1900 | lime             | 3318 |
| red rock                   | 1905 | shale            | 3321 |

lime 3327  
lime 3328

SAMPLE LOG.

shale red & lime 3348  
conglomerate 3353  
sdv shale green 3365  
shale green and red 3370  
shale green 3377  
dolomite 3393 $\frac{1}{2}$   
TD.

Plug back to 3392.  
1st oil 3390  
Pay 3390-92  
7-17-34 Swab 212 B.O. 7H.  
Trace water.  
7-28-34. Pump 200 B.O. and  
110 B.W. 24 hours.  
Potential test.