

State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

S. 16 T. 16 R. 10 ^W
Loc. 530' FWL & 990' FNL SW
County Ellsworth

API No. 15 — 053 — 20,406
County Number

Operator
Sid Tomlinson

Address
Box 594 Twin Falls, Idaho 83301


Well No. #1 Lease Name Kozisek "B"

Footage Location SW/4
990 feet from (N) line 530 feet from (W) line

Principal Contractor H-30 Drilling, Inc. Geologist J.E. Jespersen

Spud Date 6-11-75 Total Depth 3408 P.B.T.D. 3386

Date Completed 8-1-75 Oil Purchaser Koch



Elev.: Gr. 1899

DF - KB 1904

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	32#	377	Reg.	225	2% gel, 3% CaCl
Production	7 7/8	5 1/2	14#	3407	Poz	120	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Jets	3357-61

Size	Setting depth	Packer set at
2 1/2	3382	none

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gals acid, 15% NE	3357-61

INITIAL PRODUCTION

Date of first production <u>6-28-75</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>60</u> bbls. Gas <u>0</u> MCF Water <u>170</u> bbls. Gas-oil ratio <u>0</u> CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s) <u>Arbuckle 3357-61</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
SID TOMLINSON

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
OIL

Well No.
1

Lease Name
Kozisek "B"

S 16T16 R10 W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST#1 3335-67 (Arbuckle) 30/30/30/30 Rec. 2700' free oil & 60' watery mud. FP 172#- 969# ISIP 1016# FSIP 1031# Dresser Atlas ran Gamma Ray/Neutron log. (cased hole log)			Electric Log	Tops:
			ANHYDRITE	672
			HEEBNER	2929
			BRN. LIME	3034
			LANSING	3050
			ARBUCKLE	3350
			T.D.	3408

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Sid Tomlinson
Signature

OPERATOR

Title
8/28/75
Date

515044