


17-16-10W

AERO PARTS MANUF. CO.
Horejsi No. 1.

SEC. 17 T. 16 R. 10 W
CNW NE
150' NW of CNW NE

County. Ellsworth

Total Depth. 3365'
Comm. 2-26-43 Comp. 5-20-43
Shot or Treated.
Contractor. Ingling & Parker
Issued. 6-12-43



CASING:
8 5/8" 363'
5 1/2" 3357'

Elevation.

Pot.

Production. Est. 350 B.

Figures Indicate Bottom of Formations.

surface clay & shale	115
sand	130
shale & sand	394
lime	400
shale, shells, red rock	940
shale & shells	1375
shale & lime	1510
sharp sdy lime & shale	1560
shale & lime	1825
sand sharp hd	1845
lime sdy	1865
shale & shells	2205
pyratise sand	2230
shale & lime shells	2285
shale & shells	2485
shale & lime	2530
shale & shells	2600
shale & lime	2680
lime	2710
lime cherty	2720
lime	2875
lime & shale	2915
lime	2945
lime & shale	3050
lime	3265
lime & shale	3335
lime	3352
Simpson	3357
Arbuckle	3365
Total Depth.	