

17-16-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company. CURRIER & ASSOCIATES  
Farm. Horejsi No. 1

SEC. 17 T. 16 R. 10W  
NW SE SW

Total Depth. 3380  
Comm. 8-6-55 Comp. 8-17-55  
Shot or Treated.  
Contractor. Sterling Drilling Co.  
Issued. 10-22-55

County Ellsworth  
KANSAS



Elevation. 1892

Production. 25 BOPD

CASING:

8 5/8 360' w/ 175 sx cmt.  
5 1/2 @ 3380' w/ 50 sx cmt.

Figures indicate Bottom of Formations.

shale & sand	360
shale & red bed	680
anhydrite	710
shale & shells	1190
lime & shale	1665
lime	1890
lime & shale	1970
lime	2105
lime & shale	2765
lime	2905
shale & lime	3090
lime	3355
conglomerate	3363
lime	3380
Total Depth	

TOPS:  
Heebner 2940  
Lansing 3040  
Arbuckle 3360

Perf. 3363-76 w/ 3 BPF, acid. 250 gal.  
tested 15 GOPH, NW/4 hrs. Acid. 1000  
gal, tested 18 GO & 6 GWPH. acid  
2000 gal. Tested 3 BOPH