

17-16-10w


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STERLING DRILLING COMPANY
Farm- Horejsi No. 2

SEC. 17 T. 16 R. 10W
SE SE SW

Total Depth. 3365'
Comm. 9-5-56 Comp. 10-5-56
Shot or Treated.
Contractor. Sterling Drilling Company
Issued. 10-20-56

County Ellsworth
KANSAS



Elevation. 1886' RB

Production. 15 BOPD

CASING:

8 5/8" @ 367' w/175 sx cem.
5 1/2" @ 3353' w/50 sx cem.

Figures indicate Bottom of Formations.

clay & shale	250
shale	368
shale & red bed	675
Anhydrite	700
red bed & shale	740
shale	1160
shale & limestone	1580
limestone	1870
limestone & shale	2025
shale	2235
shale & sand	2480
shale & limestone	2615
limestone	2965
sand & limestone	3090
limestone	3225
limestone & shale	3355 RTD
limestone & shale	3365
Total Depth	

TOPS:

Heebner	2919
Brown Lime	3025
Lansing	3043
Arbuckle	3347

CABLE TOOLS

M.I.C.T. Swabbed hole down & drilled cem. Drilled new hole to 3365' Acidized w/500 gal. Swabbed tested at rate of 15 B.F.P.H. est. 60% wtr. P.O.P.