

77-16-10W


PHILLIPS PETROLEUM CO.
Horejsi No. 1.

SEC. 17 T. 16 T. 10W.
SEc NE

Total Depth. 3380
Comm. 7-27-38 Comp. 9-28-38
Shot or Treated. 500 gal acid.
Contractor.
Issued. 11-5-38

County Ellsworth.

NOV 5 1938



CASING.

10" 372' 7" 3365'

Elevation.

Production. Pot. 164 B.
no wtr.

Figures Indicate Bottom of Formations.

surface clay and rock	65	
shale and shells	230	
shale blue and shells		
shale sticky	295	
sand and shale	320	
shale and shells	565	
shale and rock	625	
shale and iron	675	
anhydrite	692	Top of Anhydrite 675
shale and shells	1210	
shale and salt	1375	
shale and shells	1405	
lime grey broken in spots	1763	
sand	1777	
lime sdy	1855	
pyrites of iron, sdy		
lime	1870	
broken lime	1950	
broken lime and shale	2050	
broken lime	2340	
shale and shells	2465	
lime and shale	2505	
shale and shells	2605	
lime and shale	2645	
broken lime	2705	
lime hard	2970	
broken lime	2992	
shale	3020	
shale and lime	3065	
lime hard	3175	Top Lansing K.C. 3030
limo and pyrites of iron	3180	
limo mod hard	3325	
limo and shale	3349	
limo and chert	3359	
conglomerate	3362	
3362 equals 3365 S.L.M. Correction.		
arbuckslo limo	3380	Top of Arbuckslo 3365
Total Depth.		