

Mallard JV, Inc.
P.O. Box 1009
McPherson, KS 67460

17-16-10W

DRILLERS' LOG

OPERATOR: John Jay Darrah, Jr.
412 E. Douglas, Suite One
Wichita, KS 67202

WELL: Kice/Svoboda #1

API#: 15-053-21,046

COMMENCED: 6-23-88

LOCATION: E/2 SE NE

COMPLETED: 6-28-88

3300 Ft. FSL, 330 Ft. FEL

TOTAL DEPTH: 3403 Ft.

Sec. 17 Twp. 16 S. Rge. 10 W

ELEVATION: 1907 Ft. G.L.

COUNTY: Ellsworth

1915 Ft. K.B.

FORMATION

	<u>FROM</u>	<u>TO</u>
Surface	0'	218'
Shale	218	2282
Shale, Lime	2282	3403 R.T.D. Arbuckle

JUL 27 1988
KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

REMARKS

Cut 12 1/4" hole to 218' and ran 15 joints 8-5/8" x 23# x 205.71' surface casing. Set at 215.71' and cemented w/125 sacks 60/40 Pozmix, 3% cc, 2% gel. P.D. @ 5:30 a.m. 6-24-88.

Ran 2 DST's.

Ran 89 joints 5 1/2" x 14# x 3407.65' production casing. Set at 3402.5' and cemented w/75 sacks 60/40 Pozmix, 18% salt, and 3/4 of 1% FRH, 20 bbl salt flush preceding. Displaced w/82 bbl. water. Land plug w/1000# @ 3394' @ 2:45 a.m. 6-28-88.

STATE OF KANSAS)

) SS:

COUNTY OF McPHERSON)

I, BRYAN HESS of MALLARD DRILLING, do hereby certify that this is a true and correct copy of the log of the Kice/Svoboda #1 well as reflected by the files of Mallard Drilling.

Bryan Hess
Bryan Hess, Gen. Mgr.

Subscribed and sworn to before me this 8th day of July, 1988. RECEIVED STATE CORPORATION COMMISSION

11-15-89
My Commission Expires

Don J. Reichenbach
Notary Public JUL 28 1988

CONSERVATION DIVISION
Wichita, Kansas

