


18-16-10W

J. E. MABEE DRILLING CO.  
 Kosisok No. 1

SEC. 18 T. 16 R. 10W.  
 CNL NE SE  
 658' W 330'S E 1/4 cor.

Total Depth. 3420.  
 Comm. 5-6-40 Comp. 5-26-40  
 Shot or Treated.  
 Contractor. J. E. Maboo Drilling Co.  
 Issued. 10-19-40

County Ellsworth.



CASING.

103/4" 329'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

cellar	5	lime and shalo	3227
yellow clay	23	lime	3326
shale	176	lime and shale	3362
red rock	242	conglomerate	3376
shale brown	250	lime and shalo	3406
sand	312	Arbuckle lime	3420
shale	327	Total Depth.	
red rock	332	Top Conglomerate	3360
shale shells	430	Top Arbuckle	3395
sand iron & shells	450		
shale shells	550	Fair porosity and no sat.	3401-04
red rock & shale	608	Fair porosity and light	
shale shells	690	stain	3406-09
anhydrite	715	Fair porosity and light	
shale shells	808	stain	3410-12
shale shells and			
red rock	1037		
shale shells	1100		
salt and shale	1370		
shale and lime	1395		
broken lime	1615		
lime	1690		
lime and shalo	1780		
no log	1880		
shalo shells	1940		
lime brokon	2135		
lime and shale	2218		
lime brokon	2365		
lime	2453		
shalo	2480		
shalo shells	2 602		
shale and lime	2660		
shalo shells	2675		
lime and shale	2705		
lime brokon	2755		
lime	2948		
lime brokon	3052		
lime	3183		