

18-16-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- BENNETT & ROBERTS DRIG. CO.
Farm- Kozisek No. 1

SEC. 18 T. 16 R. 10W
SE SE SE

Total Depth. 3440'
Comm. 2-19-57 Comp. 3-3-57
Shot or Treated.
Contractor.
Issued. 5-25-57

County Ellsworth
KANSAS



Elevation. 1888' DF

CASING:

8 5/8" 346' w/200 sx cem.

Production. Dry

Figures indicate Bottom of Formations.

clay	10
Post Rock	50
shale	90
shale-shells-sand stks	220
red bed-shale	340
shale	346
shale	490
pyrite	498
shale	537
red bed-shale	710
Anhydrite lime	735
shells-shale	925
shale-lime stks	1165
shale-shells	1460
lime	1865
lime-shale	2070
shale	2525
shale-lime	2730
lime	2960
lime-shale	3054
lime	3368
lime-shale	3377
lime	3440
Total Depth	

dual packers. Open 1 hr., weak
blow 8 min., flushed tool 30 min.,
rec. 30' heavy drilling mud, no
show, BHP in 20 min., 1050 p.s.i.

DST # 3 - 3375-85 10' anchor,
dual packers. Open 1 hr., weak
blow 7 min., flushed tool in
30 min., rec. 30' mud w/few
specks of dead oil & sulfide
odor, BHP in 20 min., 990 p.s.i.

TOPS: All Meas. RB
Cimmerron Anhydrite 710
Heebner shale 2928
Toronto lime 2946
Douglas shale 2956
Brown lime 3028
Lansing Kansas City 3051
Conglomerate 3350
Arbuckle 3373

DST # 1 - 3370-75 5' anchor,
dual packers. Tool Plugged, no
test.
DST # 2 - 3369-75 6' anchor,