

NE NW NE

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
**KANSAS GEOLOGICAL SOCIETY BUILDING**  
**508 EAST MURDOCK - WICHITA, KANSAS**

COMPANY **J. S. (Sid) Tomlinson**

SEC. **21** T. **16S** R. **10W**  
 LOC. **NE NW NE**

FARM **Frevert**

NO. **2**

API # **15-053-20313**

TOTAL DEPTH **3,450'**

COUNTY **Ellsworth**


COMM. **January 20, 1973**

COMP. **January 28, 1973**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED



20  
15  
12  
13

10

**8 -5/8" 358' cemented w/225 sxs cement** ELEVATION **1,887' KB**

6

**5 1/2" 3,448' cemented w/125 sxs cement** PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

|                           |        |
|---------------------------|--------|
| Post Rock and Clay        | 153'   |
| Clay, Sand and Shale      | 364'   |
| Shale                     | 662'   |
| Anhydrite                 | 690'   |
| Shale and Red Bed         | 1,435' |
| Red Bed, Shale and Shells | 1,570' |
| Lime and Shale            | 2,000' |
| Shale and Lime            | 2,300' |
| Lime and Shale            | 2,815' |
| Shale and Lime            | 3,015' |
| Lime and Shale            | 3,088' |
| Lime                      | 3,130' |
| Lime and Shale            | 3,280' |
| Lime                      | 3,450' |
| Rotary Total Depth        | 3,450' |

LOG TOPS:

|      |      |
|------|------|
| SC   | 662  |
| HEEB | 2904 |
| BN L | 3008 |
| LANS | 3020 |
| ARB  | 3350 |
| LTD  | 3450 |
| RTD  | 3455 |

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
 \_\_\_\_\_  
 Dean Britting

State of Kansas }  
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 31st. day of January, 1973.



*Elsie Willison*  
 \_\_\_\_\_  
 Elsie Willison - Notary Public

My Commission Expires:

