


21-16-10W
Plotted Texas CO.STANOLIND OIL AND GAS CO.
C. Frevert No. 4.SEC. 21 T. 16 R. 10W.
NW SE NE 1160' N of SL
1450' E of WL.
County. Ellsworth.Total Depth. 3355
Comm. 4-21-35 Comp. 5-22-35
Shot or Treated.
Contractor.
Issued. 6-22-35

JUN 22 1935



CASING.

Rotary 0 to 3351
Cable 3351 to 3355'

133/8" 213' 7" 3349'

Elevation.

Production. Pot. 382 B.

Figures Indicate Bottom of Formations

shale and sand rock	65
sand	75
gyp and shale	175
shale	213
red rock	230
shale and shells	625
shale	649
anhydrite	675
sdv lime	690
shale	775
shale and shells	1235
salt	1290
shale and shells	1360
lime	1380
broken lime	1550
lime hard	1700
shale and shells	1740
lime	1745
broken lime	1780
sdv lime	1800
lime hard	1832
broken lime	1856
lime	1890
shale and shells	2075
shale broken lime	2090
shale and shells	2330
shale and broken lime	2353
shale	2415
lime	2450
broken lime	2510
shale	2585
lime	2650
shale	2657
lime hard	2796
lime	2965
shale	2995
lime	3000
<u>QORING FOR LANSING</u>	
shale	3013
lime - Lansing	3019
<u>DRILLING</u>	
lime	3075
broken lime	3150
lime	3195

broken lime	3222
lime	3283
lime hard	3300
broken lime	3325
<u>CORING FOR SILICEOUS LIME</u>	
broken lime	3335
shale green	3346
shale green	3349
dolomite (show oil)	3351
Top of Siliceous lime	3349 ✓
<u>CABLE TOOLS CORING</u>	
Siliceous lime	3355
Oil increase.	
Total Depth.	

5-22-35 Total depth 3355. swabbed
at rate of 20 bbls oil per hour with
no water.5-26-35. On potential test pumped
764 bbls oil and no water in 48 hrs.
Official 24 hours potential 382 B.
Potential taken thru 3" EUE tubing
with contractors steam equipment.Lansing lime 3013-3335
Siliceous lime 3349-3355