

21-16-10W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company MERCURY DRLG. CO.
Farm Boldt No. 2.

SEC. 21 T. 16 R. 10 W
SE SW SW

Total Depth. 3344
Comm. 2-24-46 Comp. 3-28-46
Shot or Treated.
Contractor. Mercury Drlg. Co.
issued. 4-27-46

County. Ellsworth
KANSAS



Rotary O-3331.71'
Cable 3331.71'-3344'

CASING:
8 5/8" 265' Cem.
5 1/2" 3325.71' Cem.

Elevation. 1853

Production. Phy. Pot. 38 B

Figures Indicate Bottom of Formations.

cellar	5
surface soil & clay	40
shale & shells	285
sand	330
shale & shells	627
anhydrite lime	645
shale & shells	1100
salt	1270
shale & shells	1340
shale & lime shells	1490
shale & shells	1645
shale & lime	1775
lime	1830
shale & lime	1905
lime	1940
shale & shells	2040
shale & lime shells	2140
shale & shells	2555
lime	2575
shale & shells	2630
lime & shale	2725
lime	2835
lime & shale	2875
lime	2905
lime & shale	2930
lime	3070
Kansas City lime	3120
lime	3323
Arbuckle lime	3344
Total Depth	

Tops:

Iansing-Kans.City 3005
"Booy" Conglomerate 3315
Arbuckle Dolomite 3324