

21-16-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL, INC.
Farm- Widner No. 1

SEC. 21 T. 16 R. 10W
NE NW SW

Total Depth. 3420
Comm. 9-8-65 Comp. 9-16-65
Shot or Treated.
Contractor. D. R. Lauck Oil
Issued. 3-19-66

County Ellsworth
KANSAS



CASING:

10 3/4" @ 321' w/195 sx.
7' @ 3275' w/125 sx.

Elevation. 1867.1 KB

Production. SWDW—Rate Satisfactory

Figures Indicate Bottom of Formations.

clay	270
shale	400
sand	500
red bed	535
red bed & shale	1035
shale & shells	1320
lime & shale	2770
lime	2865
lime & shale	2922
shale	2950
lime & shale	3033
lime	3420
Rotary Total Depth	

intermittent blow thruout. Rec. 30' mud
& show of Oil. ISIP 815#/30 min. FSIP
720#/30min. ifp 60#. FFP 75#.

DST #4 (M) 3373-3385, Opn. 1 hr. Fair
blow. Rec. 60' watery mud, 120' muddy
water. ISIP 935#/30 min. FSIP 935#/30 min.
IFP 35#. FFP 120 #.

TOPS: LOG

Heebner	2892
Toronto	2912
Douglas	2922
Brown Lime	2999
Lansing	3020
Arbuckle	3336

DST #1 (M) 3192-3203, Opn. 30 min. Weak
blow 3 min. Flush. Rec. 20' mud. BHP 575#/30
min.

DST #2 (M) 3322-3340, Opn. 40 min. weak
blow 16 min. Flush, weak blow 1 min. Rec.
25' mud. BHP 100#/30 min.

DST #3 (M) 3341-3355, Opn. 1 hr. Weak