

[Plotted Texas CO.]

22-16-10W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. SWc SE SW

Sec. 22 T 16 R. 10W

Casing Record.

County Ellsworth

JUL 22 1933

10" 1965 Farm. Stoltonberg

No. 3

20" 196 8 1/2" 2663 Company. Gypsy and Stanolind.


15 1/2" 446 65/8" 3300 Contr.

12 1/2" 945 53/16" Comm. 3-26-33

Comp. 5-25-33

Total Depth. 3317 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.



Elevation. 1834

Initial Production.

1579 B. in 24 hours.

Figures Indicate Bottom of Formations.

Date Issued. 7-22-33

Formation	Depth	Formation	Depth	Formation	Depth.
soil	05	red rock	2010	sand	3301
clay yellow	30	lime	2025	dolomite	3317
shale	120	shale	2075	Pay 3301 to 3310 and from	
sand	163	shale	2215	3313-3315	
shale white	170	lime	2220	TD.	3317
red rock	185	shale	2300		
shale	225	lime	2320	At 3317 swabbed 97 1/2 bbls	
sand HFW 225-235	2 35	shale	2325	oil 1st 3 hrs and 414 bbls	
shale	240	lime	2330	1st 12 hours.	
red rock	245	shale	2345	Aridized 1000 gallons 6-28-33	
shale	385	sand	2370	6-30-33 pumped 454 bbls oil	
sdv shale	405	1 BW 2345-70		9 hours.	
sand	415	shale	2380	7-3-33 Pumped 1579 bbls oil	
shale	470	lime	2390	in 24 hours. with no water.	
red rock	615	shale	2402		
lime	640	lime	2435		
red rock	730	red rock	2450		
shale	740	lime	2480		
red rock	855	shale	2515		
shale blue	910	lime	2545		
red rock	935	shale	2552		
shale blue	945	lime	2570		
shale blue	1075	shale	2575		
salt	1285	lime	2650		
salt and shale	1340	lime	2660		
shale	1350	shale	2665		
lime	1360	lime	2700		
lime and shale	1370	shale	2705		
lime	1465	lime	2820		
shale	1500	lime	2865		
lime	1550	shale	2875		
red rock	1570	lime	2880		
lime	1600	shale	2890		
shale blue	1605	lime	2895		
lime	1700	red rock	2905		
3 BW 1675-95		shale	2980		
red rock	1710	lime	2995		
lime	1770	shale	3005		
shale	1775	lime	3045		
lime	1790	shale	3050		
red rock	1805	lime	3090		
lime	1835	shale	3100		
shale	1840	2 BW 3080-90			
red rock	1845	lime	3165		
lime and shale	1870	sdv lime	3230		
lime and red rock	1940	lime	3265		
red rock	1965	red and grey shale and			
lime	1990	lime	3292		
shale	2000	shale G.	3298		