


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg., Wichita, Kansas.

MAGNOLIA PETRO. CO.
August Schroeder No. 2

07011 E D BY C H E
26-16-10W
SEC. 26 T. 16 R. 10W.
CWL NW SW
660' FNL 330' FWL SW $\frac{1}{4}$

Total Depth. 3303 SLM
Comm. 7-27-40 Comp. 8-19-40
Shot or Treated.
Contractor.
Issued. 10-5-40

County Ellsworth.



CASING.

103/4" 307' 5 1/2" 3298' DF

Elevation.

Production. Pot. 4499 B.

Figures Indicate Bottom of Formations. no wtr. Pumping. Echo.
Maximum Pot. 3000 B.

shale and shells	575
sand and shale	670
shale and shells	1000
salt and shale	1240
shale and shells	1390
broken lime	1445
lime	1478
lime and shale	1545
shale and lime shells	1605
shy lime & shale	1655
sand and lime	1694
shale.	1735
lime	1760
sticky shale & lime	1815
lime	1920
red bed	1940
lime	1948
shale and lime	2357
shale	2380
lime	2397
shale lime shells	2638
lime	2916
shale and lime	2922
lime	3290
T.D.w/rotary	3299 D.F.
Standardized	
Arbuckle lime	3303 SLM
Total Depth.	

Swabbed 21 BPH 1200' from top for 5 hours.
Swabbed 63 BPH 1800' from top for 4 hours.

Acidized with 500 gal.

Potential 4499 bbls by Echometer in 24 hours
pumping, no water.
Maximum Potential 3000 bbls.,

Tops: Lansing - K.C. 2987
Simpson 3290
Arbuckle lime 3298 DF