

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


26-16-10W

MAGNOLIA PETROLEUM COMPANY.
August Schroeder No. 5

SEC. 26 T. 16 R. 10W.
CEL SE SW
660 FSL 330' FEL SW $\frac{1}{4}$

Total Depth. 3324 SLM
Comm. 12-7-40 Comp. 1-3-41
Shot or Treated.
Contractor.
Issued. 2-8-41

County Ellsworth.



CASING.

103/4" 251' Cemented.
5 1/2" 3319' Cemented.

Elevation.

Production. Pot. 9732 B.
Figures Indicate Bottom of Formations. no wtr. Echometer Pumping
3000 B. Maximum.

shale and sand	80
shale and red bed	251
shale and lime	832
shale and lime	900
shale and salt	1145
shale and shells	1390
shale and sand	1437
lime	1575
shale and shells	1605
lime	1703
broken lime	1757
lime	1827
broken lime	1902
lime	1925
shale and shells	2560
lime	2889
shale	3000
lime	3220
lime and shale	3245
lime and chert	3260
lime	3306
shale	3315
sdv lime	3319
Standardized	
Arbuckle lime	3324
Filled 250' of top in 12 hours.	
acidized with 1000 gal thru 2 1/2" tubing.	

Total Depth 3324 SLM

Top of Arbuckle 3318 DF.