

27-16-10W

DRILLER'S WELL LOG

DATE COMMENCED: December 10, 1983
DATE COMPLETED: December 17, 1983

Future Oil & Exploration, Inc.
MONTGOMERY #1
C NW SE
Sec. 27, T16S, R10W
Ellsworth County, Ks.

ELEVATION: 1831 K.B.

0 - 583' Surface Soil, Red Bed, Shale
583 - 611' Anhydrite
611 - 2542' Lime & Shale
2542 - 2566' Lime
2566 - 2591' Shale & Sand
2591 - 2845' Lime
2845 - 2849' Shale
2849 - 2862' Lime & Shale
2862 - 2876' Lime
2876 - 2952' Shale
2952 - 2968' Lime & Shale
2968 - 3251' Lime
3251 - 3284' Shale, Lime, Chert, Sand
3284 - 3300' Dolomite
3300' RTD

FORMATION DATA

Anhydrite	583'
Howard	2542'
Severy	2566'
Topkea	2591'
Heebner	2845'
Toronto	2862'
Douglas	2876'
Br. Lime	2952'
Kansas City	2968'
Base K.C.	3251'
Conglomerate	3261'
Arbuckle	3284'
RTD	3300'

Surface Pipe: Set new 8-5/8"
20# pipe @395' w/185 sacks
60/40 pozmix 2% gel 3% cc.

Production Pipe: Set new 5 1/2"
17# @3296' w/100 sacks 60/40
pozmix 18% salt w/10 Bbls. salt
flush.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 19 day of December 1983.

My Comm. Expires:

4-29-86

Notary Public
Notary Public