


~~22~~ 26-16-10W

BENSON DRIG.CO.
Womhoff No. 1.

SEC.26 T.16 R.10 W
CWL SW SE

Total Depth. 3310=3320 Corr.
Comm. 10-10-42 Comp. 11-28-42
Shot or Treated.
Contractor.
Issued. 4-17-43

County. Ellsworth



CASING:

15 1/8" 324' 8" 1925'
13 3/8" 495' 7" 2965'
10" 1055' 53/16" 3310'

Elevation.

Production. Pot. 8497 B.

Figures Indicate Bottom of Formations.

soil yellow	40	lime	1972	15 BWPH 150-65
shale	150	shale	1975	HFV 210
sand	165	lime	1985	HFV 350
redrock	250	shale	2000	1/2 BW 590
shale sdy	270	lime	2015	1 1/2 BW 1650
shale brown	275	shale	2030	9 BW 1680-1710
shale blue	340	lime	2065	2 BW 2045-50
sand	350	shale & lime	2125	2BW 3075-80
shale	405	shale	2170	
sand	430	lime	2175	some gas & sm sh oil
shale	445	redrock	2182	2989-3000
mud	475	lime	2190	
red rock	480	shale brown	2205	
shale red	495	shale	2215	
red rock	570	lime	2217	
pyrite of iron	580	shale	2295	
shale red	585	lime	2310	
iron	590	shale	2360	
shale red	695	lime	2385	
red rock	825	shale	2390	
shale	880	lime	2415	
red rock	920	shale	2435	
shale	1045	lime	2450	
salt	1060	shale	2505	
salt & shale	1125	lime	2525	
lime	1135	shale	2540	
salt	1205	lime	2560	
salt & shale	1275	shale	2570	
lime	1280	lime brkn	2600	
shale	1355	shale	2610	
lime brkn	1410	lime	2700	
shale	1435	shale	2705	
lime	1470	lime	2840	
shale	1485	shale	2845	
lime brkn	1540	lime	2870	
shale blue	1550	red rock	2885	
lime	1560	shale	2938	
red rock	1580	lime	2940	
lime	1605	shale	2948	
shale	1610	lime	2955	
lime Ft. Riley	1680	shale	2965	
sdv lime	1710	lime	2984	
lime	1740	shale blk	2989	
shale	1750	lime	3025	
1750=1705 Corr. Meas.		lime brkn	3035	
shale blue	1705-1715	lime	3045	
lime	1725	shale & lime	3080	
shale	1735	lime	3265	
lime	1755	shale & lime	3270	
shale	1760	lime	3276	
lime	1775	conglomerate	3283	
red rock	1785	lime	3288	
lime	1835	conglomerate	3290	
red rock	1840	shale green	3309	
lime	1890	lime Arbuckle, sh oil	3310	
shale	1895	3310 equals 3320 Corr.		
lime	1907	Total Depth.		
red rock	1922			
lime	1945			
shale	1950			