


27-16-10W

THE TEXAS CO.  
A. Schroeder No. 1.

SEC. 27 T.16 R.10W  
CN $\frac{1}{2}$  NE SW  
660' fr EL 330' fr NL SW $\frac{1}{4}$

Total Depth. 3290'  
Comm. 4-1-40 Comp. 5-2-40  
Shot or Treated. 5000 Gals. Acid.  
Contractor. Helmerich & Payne, Inc.  
Issued. 7-6-40

County. Ellsworth



CASING: Rotary O-3277  
Cable 3277-90  
10 $\frac{3}{4}$ " 360'  
7" 3277'

Elevation.

Production. Pot. 1407 B. Deptho  
2% wtr-----Pumping

Figures Indicate Bottom of Formations.

surface rock & clay	100
clay, sand, shale	360
shale & sand	396
anhydrite	412
red rock & shale	565
lime hrd	615
shale & shells	1100
shale & salt	1270
shale	1290
lime	1340
lime hrd	1389
lime brkn	1410
shale & lime	1505
lime	1620
lime brkn	1649
shale & shells	1675
lime	1745
shale & lime	1895
shale & lime	2280
lime brkn	2370
shale & lime	2583
shale	2595
lime	2640
shale & lime	2708
lime	2906
shale	2949
lime	3064
lime sft	3078
lime	3115
lime & little shale	3190
lime	3290
Total Depth.	

Top Arbuckle 3275