


THE TEXAS COMPANY.  
A. Schroeder No. 5

Plotted Texas CO. 7  
SEC. 27 T. 18 R. 10W.  
CN $\frac{1}{2}$  NW SW  
27-16-10W

Total Depth. 3305  
Comm. 6-13-41 Comp. 7-4-41  
Shot or Treated. no acid.  
Contractor. Herndon Drilling.  
Issued. 8-9-41

County Ellsworth.



| CASING. | Rotary          | 3290 |
|---------|-----------------|------|
|         | Cable           | 3305 |
| 103/4"  | 365' cemented.  |      |
| 7"      | 3290' cemented. |      |

Elevation.

Production. Pot. 374 B.  
no wtr physical.

Figures Indicate Bottom of Formations.

|                  |      |
|------------------|------|
| shale and shells | 210  |
| shale            | 365  |
| shale and shells | 600  |
| anhydrite        | 625  |
| shale and shells | 830  |
| salt             | 980  |
| shale            | 1050 |
| salt             | 1280 |
| shale and shells | 1395 |
| broken lime      | 1920 |
| shale and shells | 2265 |
| shale and lime   | 2530 |
| lime             | 2890 |
| lime and shale   | 2970 |
| lime             | 3284 |
| shale and lime   | 3294 |
| lime             | 3305 |

Total Depth.

Top of Arbuckle 3290