

27-16-10 W
Plotted Texas CO.

THE TEXAS CO.
A. Schroeder No. 6.

SEC. 27 T. 16 R. 10 W
CSW SW
150' NE of CSW SW

County. Ellsworth

Total Depth. 3289'
Comm. 1-26-43 Comp. 2-19-43
Shot or Treated.
Contractor. Kiowa Drilg. Co.
Issued. 4-10-43 Rotary O-3277
Cable 3277-89

CASING:

10 $\frac{3}{4}$ " 353' Cem.
5 $\frac{1}{2}$ " 3277' Cem.

Elevation.

Production. Pot. 175 B. Swb

Figures Indicate Bottom of Formations.

clay & sand	45
shale & shells	140
sand	170
shale & shells	365
lime sdy	630
shale & shells	650
red bed	690
shale & shells	1265
lime & shale	1400
lime sdy	1610
shale & shells	1685
lime & shale	1755
lime hd	1797
shale & shells	2010
shale & lime	2085
shale & shells	2552
lime	2566
shale & lime	2660
lime	2810
lime cherty	2828
lime	2880
lime cherty	2885
lime	3289
Total Depth.	

Tops: Heebner	2860
Lansing	2960
Arbuckle	3276

2-19-43 swbg test 175 BO
Dumped 100 Gals. Acid in
csg to clean out hole