

27-16-10W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. TEXAS COMPANY
Farm. A. Schroeder No. 7

SEC. 27 T. 16 R. 10 W
SE NW SW

Total Depth. 3295'
Comm. 5-18-47 Comp. 6-9-47
Shot or Treated.
Contractor. Beardmore Drlg. Co.
Issued. 6-28-47

County. Ellsworth
KANSAS



CASING:

8 5/8" 375' Com. w/250 sx.
5 1/2" 3301' Com. w/150 sx.

Elevation. 1836 feet

Production. Pmpg. 358 BO, 6%
wtr.

Figures Indicate Bottom of Formations.

shale & shells	100
sand, shale & shells	369
shale & shells	1000
salt, shale & shells	1365
lime brkn	1670
lime sdy	1690
lime brkn	1850
shale & shells	2200
shale & lime	2390
lime & shale	2450
lime brkn	2685
lime	2830
lime & shale	2970
lime	3100
lime & chert	3160
lime	3292
Arbuckle lime	3295
Total Depth.	

Tops:
Lansing 2972
Arbuckle 3283

6-6-47 - Acidized w/500 gal. acid, max.
press. 950#, min. press. 450#, swbd
2 1/2 BPH after acid.
6-7-47 - Acidized w/1000 gal. acid, swbd.
222 B. in 16 hrs. after well was swbd
down.